

**DRAFT**

**U.S. Forest Service**

# OUACHITA

**National Forest**

**PROJECT SUMMARY SHEET**

*ROAD COST ESTIMATE*

TIMBER SALE  
DISTRICT  
COUNTY

**CANEY**  
**MENA**  
**POLK**

<u>ROADS</u>	<u>TYPE</u>	<u>LENGTH MILES*</u>	<u>COST</u>
1 NFSR 31	RECONSTRUCTION	0.14	\$14,492

**Total**

**0.14**

**\$14,492**

\* Length of (New/Re)constructed portion of road

Prepared By: EMG



**Aaron Cole** Digitally signed by Aaron Cole  
Date: 2022.04.25 17:17:40 -05'00'

APPROVED BY: \_\_\_\_\_

DATE: \_\_\_\_\_

SCHEDULE OF ITEMS AND ROAD COST ESTIMATE

<b>DRAFT</b> CANEY			<b>RECONSTRUCTION</b>		<b>RD 1 OF 1</b>	
(1) Road	<b>NFSR 31</b>	District	<b>MENA</b>			
Length (miles)	<b>0.14</b>	County	<b>POLK</b>			
Pay Item Number	Description	Method Measure.	Units of Measure.	Quantity	Unit Price	Cost
15101	Mobilization	LSQ	L.S.	1	\$ 4,750.00	\$4,750
20104	Clearing and grubbing, disposal of tops and limbs (F) , logs( F ), stumps (F)	CQ	Acre	0.51	\$1,820.00	\$928
30113	Aggregate surface course, Type AR-class 4, compaction method A	CQ	C.Y.	180	\$ 35.12	\$6,322
30311	Road reconditioning, surfacing, Compaction Placement Method 3	CQ	STA	7.39	\$145.00	\$1,072
62527	Seeding, Fertilizing, and Mulching, hydraulic or dry Method	CQ	Acre	0.39	\$2,360.00	\$920
63501	Temporary traffic control	LSQ	L.S.	1	\$500.00	\$500
<b><u>Road NFSR 31 Total</u></b>						\$14,492
ROAD COMPONENT 1						\$8,170
ROAD COMPONENT 2						\$6,322